

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Marb Ogmore of Terra Resources has this date requested permission to plug the following described well:

Operator's Full Name: Terra Resources

Complete Address: P.O. 839 Oklahoma City, OK 73101

Lease Name: Henshouse Well No. 1

Location: NW 4 Sec. 14 Twp. 9 Rge. 21 (E) (W)

County: Graham Total Depth: 3709

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Ogmore was instructed to plug the well as follows:

8 5/8" @ 212' w/135 or - 5 1/2" @ 3701' w/200 or - Openhole

3701-09' cast bridge plug @ 3660' - Perfo @ .3404 to 3598

Fish in hole @ 3308' - 7 ft of 2 3/8" tubing, rods & pump

squeezed @ .1135-1140' & 1145'; squeezed @ 2779 & 2967.

Ran tubing to 3308', pumped 76 or cmt & 2 hullo - pulled up to 2700'

pumped 15 or gel; pulled up to 1300'; pumped 120 or cmt &

2 hullo to surface; Hob-up to 125 or cmt + 3 hullo PSI to 400 #

Very truly yours,  
Dennis L. Hamel  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

7/20/82  
JUL 20 1982

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

JUL 20 1982