

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Graham County. Sec. 20 Twp. 9 Rge. (E) 21 (W)

Location as "NE/CNWxSWx" or footage from lines NW NW NE.

Lease Owner Specter Pipe & Supply, Inc.

Lease Name Fury A Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 7-12-50 1950

Application for plugging filed Oct. 7, 1968 1968

Application for plugging approved Oct. 8, 1968 1968


Plugging commenced 10/16 1968

Plugging completed 10/20 1968

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Arbuckle Depth to top 3804 Bottom 3805 Total Depth of Well 3812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	240 ft.	none
				5 1/2" OD	3805 ft.	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3500' with sand, dumped 5 sacks cement, set 10' rock bridge at 1100', filled to top with readymix

RECEIVED
STATE CORPORATION COMMISSION
10/28/68
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lynch Casing Pulling Co
Address Rt 4, Great Bend, Kans

STATE OF Russell, COUNTY OF Kansas, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1968

My commission expires May 21, 1971
Wilma M. Lindahl Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
805 East Murdock, Wichita, Kansas


COPY

Company - CITIES SERVICE OIL CO.
Farm - Fury "A" No. 2

SEC. 20 T. 9 R.21W
NW NW NE
330' S and 330' E of N/4 Cor.

Total Depth. 3812
Comm. 6-21-50 Comp. 7-12-50
Shot or Treated.
Contractor. R.W.Rine Drilling Co.
Issued. 9-2-50

County. Graham
KANSAS



Elevation. 2297

Production. D.D. Pot. 2770 B.O.

CASING:
8 5/8" 240' cem w/175 sx.
5 1/2" 3805' cem w/175 sx.

Figures Indicate Bottom of Formations.

clay, sand	180
shale, sand	240
shale, shells	1175
sand, shale, shells	1725
shale	1775
anhydrite	1811
shale, shells	2120
shale, lime	2365
shale, broken lime	2475
lime	2750
lime, shale	3425
lime	3750
lime, shale	3785
lime	3805
3805 RTD = 3805SLM	
lime	3812
Total Depth	

Tops:
Lansing 3500
Eros. Arbuckle 3803
Arbuckle 3804
Penetration 8

Fillup: 320' oil in 15 mins. at 3806
1760' oil in 1 hr. 20 min. 3809
2310' oil in 1 hr. 50 min. 3809
2565' oil in 2 hrs. 20 min. 3809
2720' oil in 2 hrs. 50 min. 3809
2830' oil in 3 hrs. 50 min. 3809

7-11-50 Physical potential 480 oil, no
water in 24 hrs.

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas