


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Graham County, Sec. 19 Twp. 9 Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines SWNE NE
Lease Owner Eurek a Drilling Company
Lease Name Fury B#2 Well No. _____
Office Address Hamilton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/30/69 _____ 19____
Plugging completed 2/2/69 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3847 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	280'	none
				5 1/2"	3840'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3847', rigged up over 5 1/2" casing, shot pipe at 1434', 1243', 1014', 524', 304', 170', fished wire line after each shot. Pumped 5 sacks hulls, 30 sacks of gel and 130 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1969
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of February, 1969



Margaret McCluskey
Notary Public.

My commission expires February 15, 1971

WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Fury "B"
 Location 990' South and 990' West of NE Corner Sec. 19 T. 9 R. 21W
 Elevation 2310 (2307 Gr.) County Graham State Kansas
 Drlg. Comm. August 10, 1950 Contractor R. W. Rine Drilling Company
 Drlg. Comp. August 25, 1950 Acid None
 T. D. 3847' Initial Prod. Physical Potential: 23.56 oil, 20% water, 24 hrs. (10-9-50)

CASING RECORD:

8-5/8" @ 280' cem. 175 sx cement
 5-1/2" @ 3840' cem. 175 sx cement

FORMATION RECORD:

shale, shells & sand	0-280
clay, sand & shale	800
sand, shale & shells	1795
anhydrite 18	1835
shells & shale	2080
shale & shells	2680
lime, shale, shells	3018
lime & shale	3480
lime	3824
chert, shale & lime	3838
3838 RTD = 3840 SLM	
lime	3847 T. D.

Corr. Lansing	3532' (-1225)
Corr. Cherty Congl.	3800'
Corr. Arbuckle	3838' (-1531)
Penetration	9'
Total Depth	3847' (-1540)

Fillup: 130' oil in 50 mins.
 217' oil in 1 hr. 20 mins.
 1305' oil in 13 hrs. 50 mins.

SYFO: 500' 0°
 1000' 0°
 1500' 0°
 2000' 1°
 2500' 0°
 3000' 0°
 3500' 1°

7-7/8" rotary hole.

5-8-51 Acidized with 500 gallons
 5-19-51 Pumped 33 oil 55 wtr, 24 hrs

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 16 1969
 CONSERVATION DIVISION
 Wichita, Kansas