

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-065-01955-00 00
LEASE NAME Cooley
WELL NUMBER #2
2310 FSL Ft. from S Section Line
2310 FEL Ft. from E Section Line
Sec. 17 TWP 9S RGE 21W E or (W)
County Graham
Date Well Completed 4/1/50
Plugging Commenced 5/5/03
Plugging Completed 5/5/03

TYPE OR PRINT

NOTICE: Fill out completely and return to
Coms. Div. office within 30 days.

LEASE OPERATOR Corsair Energy, LC
ADDRESS 914 E. Douglas Ave., Wichita KS 67202
PHONE # 316-267-7779
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/28/03 (date)
by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? NO if not, is well log attached? No Logs run
Producing Formation Arbuckle Depth to Top 3809' Bottom TD 3812'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing 3501						
BKC 3721		Surface	149'	8 5/8"	149'	0
Simpson 3803-3809		Surface	3810'	5 1/2"	3810'	0
Arbuckle 3809-3811						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Perforated @ 2000', 1560' and 1025'
1st Plug @ 3565' w/ 16 sk gel spacer and 40 sk 60/40 6% cement through tubing
2nd Plug @ 1665' w/125 sk 60/40 6% cement through tubing, circ to surface.
3rd Plug @ of 50 sk 60/40 6% cement down casing, squeezed to 500#.

Name of Plugging Contractor Pfeifer Dozer & Well Service LLC License No. 32579
Address 217 St. Peter St., Morland KS 67650

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Corsair Energy, LC
STATE OF Kansas COUNTY OF Sedgwick, ss.

James G. Collins (Employee of Operator) or (Operator) of above-described well
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

RECEIVED
5/21/03
MAY 21 2003


KCC WICHITA

(Signature) [Signature]
(Address) 914 E Douglas Ave., Wichita KS 67202

SUBSCRIBED AND SWORN TO BEFORE ME THIS 13th day of May 2003

Virginia Lee Smith
Notary Public
KCC My Commission Expires: August 25, 2004

MAY 16 2003
HAYS, KS



Form CP-4
Revised 05-88