

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 17 Twp. 9S Rge. 21 (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner American Petrofina Co. of Texas

Lease Name Cooley 'A'

Office Address 4613 Jacksboro Hwy., Wichita Falls, Tx. 76302 Well No. 2

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-21 1950

Application for plugging filed 4-11 1983

Application for plugging approved (Verbal) 6-20 1983

Plugging commenced 6-23 1983

Plugging completed 6-23 1983

Reason for abandonment of well or producing formation Uneconomical to operate

If a producing well is abandoned, date of last production 8-1 1976

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Arbuckle Depth to top 3823 Bottom 3829 Total Depth of Well 3829 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	177	8-5/8	177	0
		Surface	3823	5-1/2	3823	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

12 sacks sand dumped to cover the Arbuckle (8-1-76)

Pumped 270 sx 50/50 Poz. w/6% gel, 3% cc down 5-1/2

csg. Cement circulated to surface.

Witnessed by State.

~~4/14/84~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementers

Address Russell, Ks.

STATE OF Texas, COUNTY OF Wichita, ss. R. M. Albers

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) RM Albers

4613 Jacksboro Hwy., Wichita Falls, Tx. 76302 (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1983

My commission expires 6-30-84 Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock, Wichita, Kansas


**COPY**

Company - PALMER OIL CORP. & N.C.R.A.  
Farm - Cooley "A" No. 2

SEC. 17 T. 9 R. 21W  
SW SW SW

Total Depth. 3829  
Comm. 2-15-50 Comp. 3-5-50  
Shot or Treated.  
Contractor. Palmer Oil Corp.  
Issued. 4-8-50

County. Graham  
KANSAS



Elevation. 2317' *RIP*

Production. Deptho. 3000 bbls.

CASING:

8 5/8" 181' cem. w/125 sx.  
5 1/2" 3823' cem. w/100 sx.

Figures Indicate Bottom of Formations.

cellar	10	
sand	40	
sand & shale	110	
shale	253	
sand, shale, shells	920	
sand & shale	1100	
shale	1245	
sand	1265	
shale & shells	1538	
lime, shell & shale	1688	
shale & lime	1910	
shale & shells	2110	
lime & shale	2305	
lime & shale brkn	2396	
lime brkn	2590	
lime & shale brkn	2662	
shale & shells	2930	
lime & shale	3000	
shale & shells	3105	
lime	3185	
lime & shale	3271	- 954
lime	3483	- 1166
shale	3485	- 1169
lime	3701	- 1384
lime & shale brkn	3776	- 1459
lime brkn	3791	- 1474
congl.	3823	- 1506
lime Arb.	3829	- 1512
Total Depth		
Tops: R. B.		
Heebner	3483	- 1166
Lansing	3519	- 1202
Base K.C.	3733	- 1416
Marmaton chert	3788	- 1466
Simpson	3806	- 1484
Arbuckle	3823	- 1506

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1983

CONSERVATION DIVISION  
Wichita, Kansas