

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,261-00-00

LEASE NAME Cooley "A"

WELL NUMBER 14

SPOT LOCATION SE/4 NW/4 SW/4

SEC. 17 TWP. 9S RGE 21W (#) or (W)

COUNTY Graham

Date Well Completed 1/5/86

Plugging Commenced 1/5/86

Plugging Completed 1/5/86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Fina Oil & Chemical Company
1601 N.W. Expressway, Suite 900
ADDRESS Oklahoma City, Oklahoma 73118

PHONE # (405) 840-0671 OPERATORS LICENSE NO. 5692

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601 - Dale Balthazor

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing formation None Depth to top _____ bottom T.D. 4,000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	254.25'	-0-

RECEIVED
STATE CORPORATION COMMISSION
1/27/86
JAN 27 1986

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 3970' w/25 sx cement; 2nd Plug @ 1850' w/25 sx cement;
3rd Plug @ 1060' w/100 sx cement; 4th Plug @ 270' w/40 sx cement;
Bridge Plug @ 40' w/10 sx cement & 1 sx hulls; 15 sx cement in rathole;
(Plugs calculated by displacement)
215 sx 60/40 Pozmix, 4% Gel 3%CC
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Red Tiger Drilling Company License No. 5302
Address 1720 KSB Building, Wichita, Kansas 67202

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

David A. Roddy (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David A. Roddy
1601 N.W. Expressway, Ste. 900
(Address) Oklahoma City, OK 73118

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 1986

Raylene M. Smith
Notary Public

My Commission expires: 7/6/88