

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-02903-00-00

LEASE NAME Cooley

WELL NUMBER A-3

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 17 TWP. 9 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 3-20-50

Plugging Commenced 9-24-91

Plugging Completed 9-24-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR National Cooperative Refinery Association

ADDRESS 6000 W. 10th, Great Bend, KS 67530

PHONE# (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Carl Goodrow and Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3841

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
10/11/91
OCT 11 1991
CONSERVATION DIVISION
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. TIH w/open ended tubing to 2010'. Spotted 100sxs. 65/35 POZ w/10% gel and 300# hulls. Pulled tubing to 1206'. Spotted 300 sxs 65/35 POZ w/10% gel and 200# hulls. Cement didn't circulate. TOH w/tubing. Pump 100 sxs 65/36 POZ w/10% gel and 300# hulls down casing at 300#, pumped 100 sxs 65/35 POZ w/10% gel down bradenhead at 150#, last plug down at 2:00p.m. Plugged w/600 sxs total.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Haliburton License No. _____

Address Hays, Ks. 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Cooperative Refinery Association

STATE OF Kansas COUNTY OF Barton, ss.

Steve Brackeen (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Brackeen

(Address) 6000 W. 10th, Great Bend, KS 67530

NOTARY PUBLIC-STATE OF KANSAS
RHONDA MCKENZIE
My Appt. Exp. 7-18-94

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 91

Rhonda McKenzie
Notary Public

My Commission Expires: 7-18-94