

API NUMBER 5-6-50  
LEASE NAME Cooley B  
WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Berexco, Inc.  
ADDRESS Box 723 Hays, Kansas 67601  
PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

SW SE NW Ft. from S Section Line  
Ft. from E Section Line  
SEC. 17 TWP. 9 RGE. 21 (E) or (W)  
COUNTY Graham

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 5-6-50  
Plugging Commenced 1-6-95  
Plugging Completed 1-6-95

The plugging proposal was approved on 1-6-95 (date)  
by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached?                     

Producing Formation                      Depth to Top                      Bottom                      T.D. 3786

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	172	8 5/8		
	Casing	0	3770	5 1/2		

RECEIVED  
STATE CORPORATION COMMISSION  
1/13/95  
JAN 13 1995

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Cement or other plugs were used, state the character of same and depth placed, from            feet to            feet each section.  
Run tbq. openended. Pull 1 jt. to 3093.98. Spot 100 sk. 60/40 pos, 10% gel with 200# hulls.  
Pull 48 its. to 1594.52. Mix 90 sk. 60/40 pos, 10% gel with 300# hulls. Circulate to surface.  
Pull tbq. Hook to 8 5/8 mix 3 sk. cement coming out of ground. Hook to 5 1/2 mix 107 sk  
Max. pressure 250#. Shut in 100#.

Name of Plugging Contractor Berexco, Inc. License No. 5363  
Address Box 723 Hays, Kansas 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Kansas 67601



Subscribed and sworn to before me this 11 day of January, 19 95

Rosemary Smith  
Notary Public

My Commission Expires: 5-1-1995  
USE ONLY ONE SIDE OF EACH FORM