

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD


Strike out upper line when reporting plugging off formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Graham County. Sec. 17 Twp. 9 Rge. 21 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE SE SE Lease Owner. The Palmer Oil Corporation, etal Lease Name. Cooley "A" Well No. 1 Office Address. 415 Union National Bank Building, Wichita 2, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed. 5/26/49 Application for plugging filed. 5/26/49 Application for plugging approved. 5/26/49 Plugging commenced. 5/26/49 Plugging completed. 5/26/49 Reason for abandonment of well or producing formation Dry hole If a producing well is abandoned, date of last production. 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough Producing formation. Depth to top. Bottom. Total Depth of Well 3782 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Formation, Content, From, To, Size 8 5/8, Put In 173, Pulled Out none.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3782 - 170 heavy mud
170 - wooden plug
170 - 125 Cement plug 15 sacks cement
125 - 30 Heavy mud
30 - wooden plug
30 - 0 Cement plug 10 sacks cement

RECEIVED 6/8/49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Palmer Oil Corporation Address 415 Union National Bank Building Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. A. H. Smith (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) A. H. Smith

Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 19 49

Bonnie Duvall Notary Public

My commission expires 3/21/53



WELL LOG - COOLEY "A" #1

Elevation 2232 RB

WELL OWNER: The Palmer Oil Corporation, etal
 CONTRACTOR: The Palmer Oil Corporation

Section 17-95-21W
 Location: NE SE SE
 County: Graham
 Elevation: 2232 D.F.

Commenced: 5/13/49
 Completed: 5/26/49
 RESULTS: Dry Hole

Gauging Record
 8 5/8" - 173" cemented 125 sacks

Formation Tons (D.F.)

Sand & shale	0	106
Shale & shells	106	179
Shale	279	420
Shale & pyrite	420	505
Shale & shells	505	850
Sand & shale	850	930
Shale & shells	930	1675
Line	1675	1690
Anhydrite	1690	1720
Broken line & shale	1720	1850
Shale & shells	1850	2180
Line & shale	2180	2393
Line	2393	2568
Line & shale	2568	3300
Line	3300	3596
Cherty line	3596	3604
Line	3604	3765
Line & chert	3765	3779
Chert	3779	3782
Total Depth	3782	

Keokuc	3414
Lansing	3448
Base Kansas City	3664
Shaly conglomerate	3700
Cherty conglomerate	3760
Total depth in conglomerate	

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

RECEIVED *A. H. Smith*

General-Inv.

JUN - 8 1949

STATE CORPORATION
 COMMISSION

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

Subscribed and sworn to before me, a Notary Public in said county and state this 6th day of June, 1949.

Bonnie Durall
 Notary Public

My commission expires 3/21/53.

PLUGGING
 SEE NO. 17 T 9 21W
 BOOK PAGE 99 LINE 16