

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-02915-00-00

LEASE NAME Cooley

WELL NUMBER B-9

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4950 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR National Cooperative Refinery Association

ADDRESS 6000 W. 10th, Great Bend, KS 67530

PHONE# (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 17 TWP. 9 RGE. 21 (R) or (W)

COUNTY Graham

Date Well Completed 1-12-51

Plugging Commenced 10-01-91

Plugging Completed 10-01-91

The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

10/11/91  
OCT 11 1991

CONSERVATION DIVISION  
WICHITA, KANSAS

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. TIH w/open ended tubing to 2012'. Dug out Bradenhead. Spotted 100sxs 65/35 POZ w/10% gel and 400# hulls. TOH w/tubing to 1206'. Spotted 200 sxs 65/35 POZ w/10% gel and 400#hulls. Cement did not circulate. TOH w/tubing. Pumped 20 sxs 65/35 POZ w/10% gel down casing. Pumped 100 sxs 65/35 POZ w/10% gel down bradenhead. SI in w/50# on annulus. Last plug down at 1:00p.m. Plugged w/420 sxs (If additional description is necessary, use BACK of this form.) 65/35 POZ w/10% gel & 800#hulls.

Name of Plugging Contractor Haliburton License No. \_\_\_\_\_

Address Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Cooperative Refinery Association

STATE OF Kansas COUNTY OF Barton, ss.

Steve Brackeen (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Brackeen

(Address) 6000 W. 10th, Great Bend, KS 67530

NOTARY PUBLIC-STATE OF KANSAS  
RHONDA MCKENZIE  
7-18-94

Subscribed AND SWORN TO before me this 3rd day of October, 19 91

Rhonda McKenzie  
Notary Public

My Commission Expires: 7-18-94