

15-065-02913-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 6-11-50

LEASE NAME Cooley B

WELL NUMBER 6

 Ft. from S Section Line

 NE SE NW Ft. from E Section Line

SEC. 17 TWP. 9 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 6-11-50

Plugging Commenced 3-16-92

Plugging Completed 3-16-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-16-92 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3749

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	159	8 5/8		None
	Casing	0	3740	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each. Perf. 1730 and 980 2 holes each. Run tubing to 3600'. Mix 150 sk. 60/40 pos, 8% gel, 200# hulls. Pull tubing to 1600' mix 120 sk. 60/40 pos, 8% gel, 200# hulls. Cement circulate to surface. Pull rest tubing. Mix 100 sk. and pump in 8 5/8 and 100# hulls SIP 150# Hook to 5 1/2 and squeeze in 20 sks. Pressure 600#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

before me this 17 day of March, 19 92

Reemey Smith
Notary Public

NOTARY PUBLIC - State of Kansas
SUBSCRIBED AND SWORN
My Appt. Exp. 3-1-1995

My Commission Expires: 3-1-1995