

LEASE NAME Cooley B  
WELL NUMBER 5  
         Ft. from S Section Line  
         Ft. from E Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Berexco, Inc.  
ADDRESS Box 723 Hays, Kansas 67601  
PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5363

SEC. 17 TWP. 9 RGE. 21 (E) or (W)  
COUNTY Graham  
Date Well Completed 5-14-50  
Plugging Commenced 2-8-95  
Plugging Completed 2-8-95

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 2-8-95 (date)  
by Bruce Basye (KCC District Agent's Name)

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom T.D. 3820

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	172	8 5/8		
	Casing	0	3808	5 1/2		


Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each s  
rig up Mercury. Perf. 2 shots at 1670' and 990'. Run tbg. to 3548.60'. 3548.69 80 scks. 60/40  
10% gel, 200# hulls 2318.57 80 sk. 60/40 pos 10% gel 200# hulls 1162.26 75 sk. 60/40 pos. 10%  
gel 100# hulls. Circ. to surface. Hook to 8 5/8 100 sk. 60/40 10% gel 0# shut in. Hook to  
5 1/2 15 sk. 60/40 10% gel. 200# shut in.

Name of Plugging Contractor Berexco, Inc. License No. 5363  
Address Box 723 Hays, Kansas 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.  
STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed in  
the same are true and correct, so help me God.

(Signature) Ted Crawford  
(Address) Box 723 Hays, Mo. 67601  
29 day of June 19 95  
Rosemary Smith  
Notary Public



My Commission Expires: 5-1-1999  
USE ONLY ONE SIDE OF EACH FORM



PEREXCO INC.  
 970 FOURTH FINANCIAL CENTER  
 WICHITA, KANSAS 67202

0100

IDENTIFICATION#	PROPERTY NAME	DATE	INVOICE#	PAGE
KS 7147800	POTTER A LEASE	4/30/95	SUMMARY	72
ENGINEER:	COULSON, DAM E. DEKER			
UNIT	ALL PARTICIPANTS			

REF. NO.	VENDOR	DESCRIPTION	AMOUNT
		AFTER CASING POINT (ACP)	
		TANGIBLE COSTS	
BU495027	BEREXCO	TANK BATTERY TANKS 12X10	734.300
		TOTAL TANGIBLE COSTS	734.300
		TOTAL AFTER CASING POINT (ACP)	734.300
		LCE/WORKOVER	
		LEASE/UNIT OPERATING EXPENSES	
2/95	BEREXCO	ROUSTAROUT TELEPHONE EXPENSE	11.95
		TOTAL LEASE/UNIT OPERATING EXPENSES	11.95
		TOTAL LCE/WORKOVER	11.95
		TOTAL INVOICE	722.350