

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Redland Resources
Address: 6001 NW 23rd, Oklahoma City, OK 73127
Phone: (405) 789-7104 Operator License #: 32204
Type of Well: gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10/2/07 (Date)
by: Lynn Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 4973' Bottom: 5085' T.D. 5199'
Oswego Depth to Top: 4896' Bottom: 4906' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033-21433 - 00 - 00
Lease Name: Oasis
Well Number: 28-14
Spot Location (QQQQ): C of SW
1320 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 28 Twp. 32 S. R. 16 East West
County: Commanche
Date Well Completed: _____
Plugging Commenced: 10/2/07
Plugging Completed: 10/04/07

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	508'	0
				4 1/2"	5199'	3666' 3630'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4930', CIBP @ 4855', dump 2 sxs cement w/ dump bailor. Stretch and cut casing @ 3600. Lay down casing to 982'
Spot 12 sxs gel and 50 sxs cement @ 982', lay down to 550', spot 50 sxs, lay down rest of casing, run 1 jt back in and circulate cement to surface w/ 20 sxs

Name of Plugging Contractor: Clarke Corporation Inc. License #: 5105
Address: 107 W. Fowler Medicine Lodge, KS 67104
Name of Party Responsible for Plugging Fees: Redland Resources
State of Kansas County, Barber, ss.

Alan Vratil - Vratil Services Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) 509 N. Cedar Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 5 day of October, 2007
[Signature] My Commission Expires: 11/30/10
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
OCT 09 2007
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION