

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Roadrunner Energy, Inc.  
Address: 7225 S. 85 E. Ave. - Ste 100 Tulsa, OK  
Phone: 918) 250-8589 Operator License #: 04555  
Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6-21-07 (Date)  
by: Duane Kruger (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
None Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-035-~~24624~~-0000 <sup>24264-</sup>  
Lease Name: 74133-3135 Fulson  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NE - NE - SW  
2869' Feet from  North /  South Section Line  
2190' Feet from  East /  West Section Line  
Sec. 2 Twp. 35 S. R. 7  East  West  
County: Cowley  
Date Well Completed: 3-15-07  
Plugging Commenced: 6-21-07  
Plugging Completed: 6-22-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>SEE SEPARATE SHEET</u>		0	300	8 5/8"	300'	0
		0	3268	5 1/2"	3268'	1520'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rigged up to plug bottom. Sanded back to 2745', dumped 5 Sx cement to top of sand, shot pipe @ 1520', pulled out 1520' 5 1/2" casing. Loaded 40 bbls. fresh water, pumped down 1" inside 8 5/8" surface to 350' Pumped 135 Sx. cement, filled to surface. Topped off with cement.

Name of Plugging Contractor: Braden Petroleum & Well Plugging License #: 32475  
Address: 10139 SW Haverhill Road. Augusta, KS 67010

Name of Party Responsible for Plugging Fees: Roadrunner Energy, Inc.  
State of Oklahoma County, Tulsa, ss.

Dennis Clay (President) (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dennis Clay  
(Address) 7225 S. 85 E. Ave Ste 100 Tulsa, OK 74133-3135

SUBSCRIBED and SWORN TO before me this 24 day of September, 2007  
Christine Sefton My Commission Expires: 3-20-2008  
Notary Public

PWT

**ROADRUNNER ENERGY, INC.**



Fulsom #1 - Oil, Gas and Water Records

Hoover Sand	960-1032	Water
Elgin Sand	1230-1256	Water
Stalnaker Sand	1398-1536	Water
Perry Sand	1710-1756	Water
Layton Sands	1886-1903, 1940-1960, 1990-2052, 2150-2162	All these sands had Water.
Cleveland Sand	2305-2316	Water
Oswego Lime	2470-2480	Water
Mississippi Chat	2800-2807	Show of oil and gas
" Chat	2826-2838	Show of oil and gas, Both Chat zones were tested with show of oil and gas & water (non-commercial)
Arbuckle	3190 -3270	Show of oil, testsed water

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 26 2007

CONSERVATION DIVISION  
WICHITA, KS