

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Herman L. Loeb  
Address: P.O. Box 524 Lawrenceville Il, 62439  
Phone: (812) 453-0385 Operator License #: 3273  
Type of Well: gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 9/27/07 (Date)  
by: Ken Jellick (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Mississippi open hole Depth to Top: 4623' Bottom: 4652' T.D. 4652'  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-10309-00-00  
Lease Name: Wilson Estate  
Well Number: #2  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - \_\_\_\_\_ - NW  
~~660~~ 1320 Feet from  North /  South Section Line  
660 1320 Feet from  East /  West Section Line  
Sec. 20 Twp. 33 S. R. 13  East  West  
County: Barber  
Date Well Completed: 11/28/41  
Plugging Commenced: 9/27/07  
Plugging Completed: 10/1/07

KCC  
PKT  
10/12/07  
per  
oper-  
George

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4'	315'	0
				7"	4623'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9/27/07 Set 7" CIBP @ 4500'. Load and pressure test casing to 100#. Perforate @ 700'. 9/28/07 Allied Cementing pumped 400 sxs 60/40 4%, cement didn't circulate, displace cement w/ 12 bbls fresh water and SION. 10/1/07 Tag cement @ 280', perforate 4 holes @ 200' Allied Cementing pumped 120 sxs 60/40 4%, cement circulated thru 10 3/4"


RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 05 2007

CONSERVATION DIVISION  
WICHITA, KS

Name of Plugging Contractor: Pratt Well Service License #: 5893  
Address: P.O. Box 847 Pratt, KS 67124-0847  
Name of Party Responsible for Plugging Fees: Loeb Oil Company P.O. Box 524, Lawrenceville, IL 62439  
State of Kansas County, Barber, ss.  
Vratil Services Inc.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) 509 W Cedar Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 3 day of Oct, 2007

[Handwritten Signature]  
Notary Public

My Commission Expires: 11/30/10

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]