

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Kantor Oil Co., LLC.
Address: 15 W. 6th St. Suite 2602 Tulsa, OK. 74119
Phone: (620) 664-0597 Operator License #: 7116
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Mike Wilson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 079-00987 -00-00
Lease Name: Ediger
Well Number: 6
Spot Location (OQQQ): _____ - NW - SE - SW
998 Feet from _____ North / South Section Line
1334 Feet from East / West Section Line
Sec. 19 Twp. 22 S. R. 3 East West
County: Harvey
Date Well Completed: _____
Plugging Commenced: 9-25-07
Plugging Completed: 10-1-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				12"	478'	None
				8-5/8"	3333'	None
				5-1/2"	2358'	2378'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3150' & 8 sxs. cement. Cut 5-1/2' casing loose @2378' & layed down. Perf. 8-5/8" @525', ran in 525' of 2-7/8" tubing, pumped 80 bbls mud W/500# hulls & 20 sxs. gel, didn't circulate. Ran tubing to 554', circulated 200 sxs. to surface. Pumped 100 sxs. down 12". Cement fell, Circulated 8-5/8" full w/50 sxs. and 12" with 75 sxs. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Kantor Oil Co., LLC
State of Kansas County, Rice ss.

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 10 2007
CONSERVATION DIVISION
WICHITA KS


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 8th day of October, 2007

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]