

15-163-01922-00-00

API NUMBER Spud 4-18-59

LEASE NAME Pirotte

WELL NUMBER 5

890 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11TWP. 10SRGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 5-11-59

Plugging Commenced 10-30-92

Plugging Completed 10-31-92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Mustang Oil & Gas Corporation

ADDRESS 155 N. Market, #350, Wichita, KS 67202

PHONE# (316) 267-8011 OPERATORS LICENSE NO. 5652

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-31-92 (date)

by Carl Goodrow - KCC representative (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3626' Bottom 3660.5 T.D. 3670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cretaceous	Shale & Lime	0	127	8-5/8"	4 jts	none
Arbuckle	Lime	0	3669	5-1/2"	114 jts	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 100 sxs 65-35 Poz w/10% gel & 200 lbs hulls @ 3510'. Spotted 2nd plug of 100 sxs (same) @ 1935'. Spotted 3rd plug of 30 sxs (same) @ 500'. Pumped 40 sxs (same) cmt dwn csg. Pressured to 1000 psi. Plugged with total of 270 sxs cmt.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Oil & Gas Corporation License No. 5652

Address 155 N. Market, #350, Wichita, KS 67202

RECEIVED  
 11-06-1992  
 NOV 6 1992

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss. Wichita, Kansas


Stan Brady - Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stan Brady  
 (Address) 155 N. Market, #350, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 92

Kandy Hanson  
 Notary Public

Kandy Hanson



Commission Expires: 11-6-94