

15-163-20313-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County, Sec. 23 Twp. 10 Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Thunderbird Drilling, Inc.

Lease Name Collins Well No. 1

Office Address 4328 East Kellogg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 26 19 70

Application for plugging filed June 26 19 70

Application for plugging approved June 26 19 70

Plugging commenced June 26 19 70

Plugging completed June 26 19 70

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3733 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with heavy mud to 660' - 70 sacks cement
Mud to 240' - 20 sacks cement
Mud to 40' - plug & 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

06-29-1970

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner

(employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So Help me God.

(Signature)

Suite 250, 200 West Douglas, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of June, 19 70

commission expires December 14, 1973

Notary Public.

15-163-20313-00-00

DRILLERS LOG

#1 COLLINS
NW NW NW Section 23-10S-19W
Rooks County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1970
CONSERVATION DIVISION
Wichita, Kansas
06-30-1970

OPERATOR: Thunderbird Drilling, Inc.
4328 East Kellogg
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas

COMMENCED: June 17, 1970

COMPLETED: June 26, 1970


CASING RECORD: 8-5/8" @ 250' w/200 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	250	Sand and shale
250	920	Shale and shells
920	970	Shale
970	1170	Sand
1170	1505	Shale and red bed
1505	1535	Anhydrite
1535	1585	Shale
1585	2060	Shale and lime
2060	3264	Lime and shale
3264	3426	Shale and lime
3426	3733	Lime
3733		Rotary Total Depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)


I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 29th day of June, 1970.

My commission expires:
December 14, 1973


Notary Public