

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED STATE CORPORATION COMMISSION

9/30/74 SEP 30 1974

CONSERVATION DIVISION Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John P. Jennings,

Complete Address: 200 E. First Street, Wichita, Kansas.

Lease Name: Thompson Well No. 1

Location: CS/2-S/2-NE Sec. 7 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3825' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

277'--8 5/8" Surface casing, cement circulated with 170 Sx. Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 285' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Handwritten signature of W. L. Nichols

Conservation Division Agent