

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 3 1964

3-3-64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Glenn Hall of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:  
Jenkins-Ray Supply

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Jenkins- Ray Supply,

Complete Address: Box # 967, Ponca City, Oklahoma.

Lease Name: H. Kolste Well No. 1

Location: NE-NE-SE. Sec. 16 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 4216 Oil Well

Gas Well  Input Well  SWD Well X D & A  Lost Hole

Mr. Hall was instructed to plug the well as follows:

246'--13" Surface pipe, cement circulated. 1487'--9 5/8"  
intermediate string, cement circulated. 4034'--7" long  
string, cemented with 600 Sx.

Set plug @ 4010', sand to 4000' and set 6 Sx. cement with  
dump bailer. Pull 7" to 600' and circulate heavy gel mud,  
pull 7" to 540' and displace 30 Sx. cement thru 7". Pull 7"  
to 240' and displace 30 Sx. cement thru 7". Pull 7", set rock  
bridge @ 30' and 15 Sx. cement to bottom of cellar.

Very truly yours,

*W. A. Nichols*