

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
12/20/71
DEC 20 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company has this
date requested permission to plug the following described well:Mr. Lindsay guarantees payment of the plugging fee.Operator's full Name: Cities Service Oil Company,Complete Address: Box #553, Russell, Kansas.Lease Name: Morel Well No. B-2Location: NW-SW-NE Sec. 22 Twp. 9 Rge. (E)(W) 21County: Graham Total Depth 3819' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Lindsay was instructed to plug the well as follows:

152'--8 5/8" Surface casing cement circulated with 100 Sx.
3808'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug
back. Top perforation @ 3508'. 5 1/2" casing has been squeezed thru hole
in casing @ 1050' to surface. No attempt to recover casing.

Squeeze 5 1/2" casing with 2 sacks hulls, 30 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

Conservation Division Agent