

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
10/28/68
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Darnall Well No. 1

Location: App. CNE-NW Sec. 22 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3794 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

156'--8 5/8" Surface casing, cement circulated with 125 Sx.
3792'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3770'. Top perforations @ 3491'. 5 1/2" squeezed from Anhydrite to surface with cement.

Run tubing to bottom and displace 40 Sx. cement thru tubing. Pull tubing to 3400' and circulate heavy gel mud. Pull tubing to 1000' and displace 45 Sx. cement thru Tubing. Pull tubing to 180' and displace 10 Sx. cement thru tubing. Pull tubing and 5 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent