

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
10/11/65
OCT 11 1965
Conservation Division
Wichita, Kansas

Dear Sir:

Mr. Ben Thompson of Apex Csg. Pulling Co. has this

date requested permission to plug the following described well:
Drlls. & Prod. Pipe & Sup. Co.

Mr. Thompson guarantees payment of the plugging fee.Operator's full Name: Drillers and Producers Pipe and Supply,Complete Address: Box #368, Great Bend, Kansas.Lease Name: Sutor Well No. A-1Location: NW-NE-SE Sec. 22 Twp. 9 Rge. (E)(W) 21County Graham Total Depth 3805 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Thompson was instructed to plug the well as follows:

156'--8 5/8" Surface pipe, cement circulated with 125 Sx.
3794'--Production casing cemented with 100 Sx. No Per-
forations, no plug back. 11' open hole.

Pull 5 1/2" casing. Tie on 8 5/8" surface pipe and squeeze
with 35 Sx. gel followed by 75 Sx. cement.

Very truly yours,

H. A. Nichols
Conservation Division Agent