



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

3/1/65
MAR 1 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Earl Mabry of Cities Service Oil Co., has this date requested permission to plug the following described well:

Mr. Mabry guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Davignon Well No. 2

Location: NW-NE-NW Sec. 20 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3839 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mabry was instructed to plug the well as follows:

--8 5/8" Surface pipe, cement circulated.
3836'--5 1/2" Production casing cemented.
Top Perforations @ 3520'. 5 1/2" Squeezed from 1100' to surface
with 213' Sx. cement.
Sand well back to 3496' set bridge and 2 Sx. cement with dump bailer.
Push plug to 550' set bridge and 2 Sx. cement with dump bailer.
Set bridge @ 40' and 4 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent