

15-065-02986-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2/20/65
FEB 20 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Company,

Complete Address: Box #405, Chase, Kansas.

Lease Name: Van Loenen Well No. 2

Location: NW-NW-SW Sec. 19 Twp. 9 Rge. (E)(W) 21

County Graham Total Depth 3890 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

220' -- 3 5/8" Surface pipe, cement circulated with 165 Sx.
3885' -- 5 1/2" Production casing cemented with 125 Sx. Open hole
Completion. Chem-Pack behind 5 1/2" from base of Dakota Sands.

Sand well back to 3875' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing, set bridge @ 225' and fill to bottom of cellar
with Redi-Mix cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent