

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
CONSERVATION DIVISION  
3/20/67  
MAR 20 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box # 553, Russell, Kansas.

Lease Name: Pricer Well No. 2

Location: NW-NE-NW Sec. 19 Twp. 9 Rge. (E)(W) 21

County Graham Total Depth 3864 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Blandin was instructed to plug the well as follows:

244'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
3858'--5 1/2" Production casing cemented with 175 Sx. Well  
plugged back to 3854'. Well squeezed from 1165' to surface.  
Top perforations @ 3548'.

Push plug to 3500' and sand back to 3480' then set 5 Sx. cement  
with dump bailer. Set rock bridge and fill to surface with  
Redi-Mix cement.

Very truly yours,

\_\_\_\_\_  
Conservation Division Agent