

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2/4/69
FEB 4 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Csg. Pulling Co. Inc., has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Eureka Drilling Company,

Complete Address: Box #157, Hamilton, Kansas.

Lease Name: Fury Well No. B-1

Location: NE-NE-NE Sec. 19 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3856 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.
3849'--5 1/2" Production casing cemented on bottom with 175 Sx. Well plugged back to 3854'. Open hole completion. 5 1/2" had been squeezed @ 1492' with 133 Sx. cement and @ 1234' with 119 Sx.

sand well to 3840' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls plus 30 sacks gel and 130 Sx. cement staged.

Very truly yours,

M. L. D. D. D.
Conservation Division Agent