



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1972
1-3-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation,

Complete Address: Box #1934, Oklahoma City, Oklahoma.

Lease Name: Balthazor Well No. 5

Location: CS/2-SW-NE Sec. 23 Twp. 9 Rge. (E)(W)21

County: Graham Total Depth 3792' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated.

3778'--5 1/2" Production casing cemented on bottom with 150 Sx. No plug back nor perforations indicated. (5 1/2" casing collapsed @ 1870'.

Push plug to 1870' sand back to 1850' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent