

R

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company, has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box #553, Russell, Kansas.

Lease Name: Lewis Well No. B-2

Location: SE-SW-SW Sec. 23 Twp. 9 Rge. (E)(W)21

County: Graham Total Depth 3810 Oil Well X

Gas Well Input Well AWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

283'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3808'--5 1/2" Production casing cemented on bottom with 150 Sx. Well squeezed thru leak @ 1329' with 119 Sx. cement. No plug back.

Run measuring line and establish amount of sand in bottom of well, if well is sanded back into casing squeeze 5 1/2" casing with 20 Sx. gel plus 5 sacks hulls and follow with 75 Sx. 50-50 Pozmix plus 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
10-16-68
OCT 16 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

V. L. Dehler
Conservation Division Agent