

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-24-70
FEB 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orr of Kathol Petr. has this date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Kathol Petr., Inc.

Complete Address: 900 Sutton Place Wichita, Ks.

Lease Name: McClellan Well No. 7

Location: SW NE NE Sec. 8 Twp. 9 Rge. (E)(W) 19

County: Rooks Total Depth 3492' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Orr was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' and displace
70 sk cmt thru drill pipe. Heavy mud to 200' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Massey
Conservation Division Agent