

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23315-00-00  
Spot: E2SESWNW Sec/Twnshp/Rge: 20-9S-20W  
3005 feet from S Section Line, 4100 feet from E Section Line  
Lease/Unit Name: NEIL Well Number: 1  
County: ROOKS Total Vertical Depth: 3968 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

Conductor Pipe: Size feet: \$128.96  
Surface Casing: Size 8.625 feet: 264  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 02/23/2001 7:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 02/23/2001 10:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3875' w/25 sxs.  
2nd. Plug at 1850' w/25 sxs. Anhydrite 1818' - 1860'.  
3rd. Plug at 1125' w/100 sxs. Dakota 813' - 1113'.  
4th. Plug at 315' w/ 40 sxs. Surface pipe to 264'.  
5th. Plug at 40' w/ 10 sxs.  
Rat hole with 15 sxs.  
Mousehole with 10 sxs.


INDEXED  
DATE 03-15-2001  
FILE NO. 200104-1505

RECEIVED  
STATE CORPORATION COMMISSION  
3/15/01  
MAR 15 2001  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed   
(TECHNICIAN)

MAR 13 2001