

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02252-00-00  
Spot: CNWSENW Sec/Twnshp/Rge: 19-9S-20W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: COPELAND Well Number: 9  
County: ROOKS Total Vertical Depth: 3817 feet

Operator License No.: 9449

Conductor Pipe: Size feet: 8 1/2 24.05

Op Name: GREAT EASTERN ENERGY & DEV. COR

Surface Casing: Size 10 feet: 170

Address: 500 W. TEXAS STE 955  
MIDLAND, TX 79702

Production: Size 5.5 feet: 3811

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/04/2002 8:00 AM

Plug Co. License No.: 9449

Plug Co. Name: GREAT EASTERN ENERGY & DEV. CORP.

Proposal Rcvd. from: MICHAEL DAVIGNON

Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 20 sxs gel - 500# hulls.  
5 1/2" liner 1967' w/375 sxs.  
Casing squeeze at 1175' - 1045' w/280 sxs. 2730' - 2750' w/90 sxs.

Plugging Proposal Received By: DENNIS HAMEL

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/04/2002 11:00 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing - spotted 20 sxs gel followed with 40 sxs cement plus 300# hulls.  
Pulled tubing to 1800' - spotted 75 sxs cement.  
Pulled tubing to 1100' - spotted 75 sxs cement - cement at surface.  
POOH with tubing and squeezed casing with 25 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
Squeezed casing annulus to 500# - No cement.

RECEIVED  
5/20/02  
MAY 20 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-21-02

INV. NO. 2002061819

MAY 13 2002

SINCLAIR OIL & GAS #9 COPELAND 19-9-20W 22 NW SE NW


Contr. \_\_\_\_\_ ROOKS County

E. 2255 Comm. \_\_\_\_\_ Comp. 11-30-51 IP 294 BOPD (ARB) PHY POT

Tops	Depth	Datum
Arh		
LANS	3523	-1268
CONG	3781	-1526
SIMP	3801	-1546
ARB	3810	-1555
T.D.	3817	-1562

Casing  
 10" 170 CO 3817  
 5" 3811 *line* SWB 15 BOPH

GRA-ROOK POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS