

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02249-00-00  
Spot: CNENWSW Sec/Twnshp/Rge: 19-9S-20W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: COPELAND Well Number: 5  
County: ROOKS Total Vertical Depth: 3832 feet

Operator License No.: 9449 Conductor Pipe: Size feet: 124.54  
Op Name: GREAT EASTERN ENERGY & DEV. CORP Surface Casing: Size 10.75 feet: 255 130 SX  
Address: 500 W. TEXAS STE 955 Production: Size 7 feet: 3825 200 SX  
MIDLAND, TX 79702 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/02/2002 9:00 AM

Plug Co. License No.: 9449 Plug Co. Name: GREAT EASTERN ENERGY & DEV. CORP.

Proposal Rcvd. from: MICHAEL DAVIGNON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Perf casing 2300' - 1825' - 1100' - 200'.  
Ordered 350 sxs 60/40 pozmix - 10% gel - 48 sxs gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/02/2002 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 3800'.  
Spotted 48 sxs gel (96+ bbls), followed with 50 sxs cement with 300# hulls.  
Pulled tubing to 2325' - spotted 125 sxs cement with 200# hulls.  
Pulled tubing to 1125' - spotted 50 sxs cement with 100# hulls.  
Pulled tubing to 200' - spotted 40 sxs cement to circulate at surface.  
POOH with tubing and R.U. cementers to 7" casing.  
Squeezed 65 sxs cement down casing.  
Max. P.S.I. 400#. Circulation at surface. Shut in: R.U. to 10 3/4" S.P.  
Pumped 10 sxs down annulus.  
Job complete.

RECEIVED  
4/15/02  
APR 15 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE 4-16-02

INV. NO. 2002061656

Form CP-2/3

APR 04 2002

SINCLAIR OIL & GAS CO. #5 COPELAND 19-9-20W 22  
 NE NW SW

Contr. \_\_\_\_\_ ROOKS County

E 2285 Comm. \_\_\_\_\_ Comp. 8-11-50 IP 3000 BOPD  
 DRAW DOWN

Tops	Depth	Datum
Ark	1790	
	1835	
LANS	3550	-1265
CONG	3807	-1522
SIMP	3817	-1532
ARB	3826	-1541
T.D.	3832	

Casing  
 10" 255 2000' OIH/1 HR  
 7" 3825

GRA-ROOK POOL


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS