

6-27 15-163-02247-00-00 166  
R

6 041186

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 10-49  
SW SW NW, SEC. 19, T 9 S, R 20 W/E

2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Copeland Well # 3

Operator: Pet Prod Management Inc.  
Name & Address: 209 East William  
Suite 200  
Wichita, Ks. 67202

County 128.25  
Rooks  
Well Total Depth 3946 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 485 w/250 sks

Abandoned Oil Well xx Gas Well            Input Well            SWD Well            D&A           

Other well as hereinafter indicated           

Plugging Contractor R. I. Titagn License Number           

Address Oakley, Ks.

Company to plug at: Hour: 2:00 PM Day: 27 Month: June Year: 19 90

Plugging proposal received from Steve Park

(company name) P.P.M. (phone)           

were: 5 1/2 casing set at 3938 w/250 sks. PBD 3891.

Perf at 3545 - 3842.

Ordered 400 sks 65/35 poz 10% gel w/1/2 lbs. f.c. plus 200 lbs.

hulls and 20 sks gel.

RECEIVED  
STATE CORPORATION COMMISSION  
7/19/90  
JUL 19 1990

Plugging Proposal Received by            (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part            None           

Operations Completed: Hour: 8:30PM Day: 27 Month: June Year: 19 90

ACTUAL PLUGGING REPORT R.I.H. w/tubing to 3712; pumped 55 sks 65/35 poz

110% gel w/1/2 lbs. f.c. plus 2 sks hulls: Pull up to 3400 and pump 33 bbls  
gel mud; pull up to 1850 and perf 3 holes; pump 80 sks cement:

Pull up to 1050 and perf three holes. Pump 110 sks cement to circ at surface:

P.O.O.H. Sq 5 1/2 casing w/75 sks cement. Pump 75 sks cement in 8 5/8-5 1/2 annulus; Max  
800 lbs. S.I. 700 lbs. Hook up to 5 1/2 sq add 50 sks cement. Max 400 s.i. 100 lbs.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 7-27-90

INV. NO. 28783

J.L.S.

Signed Dennis L. Hamel  
(TECHNICIAN)

Dennis L. Hamel