

4 050051

6-26

T6: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-20602-00-00
SE SW NW, SEC. 19, T 9 S, R 20 W/EX

2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Copeland Well # 10

Operator: Petroleum Production Management
Name & Address Box 11320

County _____ Rooks 123.96
Well Total Depth 3814 feet

Kansas City, Mo 64112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Services License Number _____

Address _____

Company to plug at: Hour: 9:00 AM Day: 26 Month: June Year: 19 90

Plugging proposal received from Steve Park

(company name) _____ (phone) _____

were: Order 350 sks 65/35 poz 10% gel.

Well record 8 5/8 at 223' 5 1/2 at 3813

D.V. at 1818. Top of cement at 600'.

5/14/90

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00PM Day: 26 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Bridge at 2400'. Ran tubing to 2395.

Pumped 55 sks cement. 5 1/2 cir fluid. Pulled tubing to 1565. Ptmped 55 sks cement 5 1/2 circ
fluid. Pulled tubing to 885. Pumped 50 sks cement. 5 1/2 circ cement. Pulled rest of
tubing sq 5 1/2 w/125 sks cement 550 lbs. Max psi 350 lbs. Shut in psi. Sq backside w/65
sks cement 250 lbs. Max psi 200 lbs. Shut in psi.

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-9-90

INV. NO. 28563

gls

Signed Marvin Miller
(TECHNICIAN)
Marvin Miller