

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5/9/62
MAY 9 1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: NE SW NE Sec. 19 Twp. 9 Rge. _____ (E) _____ (W) 20

Name of Field: _____ Total Depth: 3885

I have this date completed supervision of plugging of:

Lease Name: Balthazor Well No. 1

Operator's Full Name: Wentworth Oil & Development Co

Complete Address: 4816 E Lewis Wichita, Kansas

Plugging Contractor Southwest Casing Pulling

Address: Great Bend, Kansas License No. 309

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A x

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No x

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 4 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 243' circulated with cement - 5 1/2" 3885' with 75 sax cement - perf 3870'
Filled with sand to 3860', set 4 sax cement with dump bailer - pulled 2900' 5 1/2"
to 500', circulated hole with heavy gel mud through 5 1/2" at 500' (35 sax Gel),
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 190', displaced 20 sax
cement through 5 1/2" at 190', heavy mud to 35', set cement 35' to 0'.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 5/16/62
INV. NO. 4940-W