

4-060843

2-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,409-00-00

SW NW NE /4 SEC. 19, 09 S, 20 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5363

Lease: Balthazor Well # 7

Operator: Berexco, Inc.

County: Rooks

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3810 ^{123.83} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 278 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 1:00 P.M. Day: 23 Month: February Year: 1996

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 375 sxs 60/40 posmix - 10% gel and hulls.
Plug with tubing.
Emergency permission to plug with rig over hole.

RECEIVED
KANSAS CORP COM
MAR 29 11:16 AM '96


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:30 P.M. Day: 23 Month: February Year: 1996

Actual plugging report: 8 5/8" to 278' w/200 sxs. 5 1/2" to 3808' with 75 sxs.
Squeezed at 1177' with 125 sxs - 1539' - 2236' with 250 sxs - 2918' - 3262' with 250 sxs.
Ran tubing to 3800' and pumped 90 sxs cement with 400# hulls. Pulled tubing to 2496' and
pumped 90 sxs cement with 200# hulls. Pulled tubing to 1268' and circulated cement with 100
sxs. Pulled tubing and tied onto annulus and pumped 75 sxs cement with 100# hulls. Tied
onto production casing and pressured to 200# Max. P.S.I. S.I.P. 200#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES CALC NO Dakota plug: YES NO
Plugged through TUBING CASING Elevation: 2279 GL

I did not [X] observe the plugging.


(agent)

INVOICED
DATE MAR 05 1996
44937
APR 26 1996