

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21446-00-00
Spot: CE2E2SW Sec/Twnshp/Rge: 19-9S-20W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease/Unit Name: COPELAND Well Number: 1
County: ROOKS Total Vertical Depth: 3970 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size feet: 8 1/2 9.03
Surface Casing: Size 8.625 feet: 226 w/150 sxs cmt
Production: Size 5.5 feet: 3968 w/175 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/02/2002 10:00 AM
Plug Co. License No.: 9449 Plug Co. Name: GREAT EASTERN ENERGY & DEV. CORP.
Proposal Rcvd. from: MIKE DAVIDGON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 10% gel - 20 sxs gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/02/2002 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Squeezed 5 1/2" casing with 40 sxs cement and 300# hulls, followed with 20 sxs gel with 200# hulls, followed with 185 sxs cement.
Max. P.S.I. 800#. S.I.P. 500#.
8 5/8" S.P. - pressured up to 500#.

RECEIVED

AUG 16 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

8-19-02

INV. NO.

2003060242

AUG 07 2002

replacement card

BIRD ENTERPRISES
PLAINVILLE KS 67663

19-09S-20W
C E/2 E/2 SW

1 COPELAND

site: 1-1/2 W OF PALCO KS
contr: PIONEER DRILLING
opd: PAT BALTHAZOR

ty: ROOKS
field: GRA-ROOK

API 15-163-21446

fr date 09/25/81 spd date 10/19/81 orig comp 10/26/81 card issued 11/18/82 last revised 06/03/96

ELV: 2303 GL DRLRS
 tops.....depth/ datum
 ARB.....3865 -1562
 RTD.....3970 -1667

IP status:
 OIL, P 6 BOPD, LKC , INTV NA , ARB 3865-3875
 11/12/82
 INFO RELEASED: 6/3/96 - WAS TEMP COMP
 CSG: 8-5/8" 226 / 150 SX, 5-1/2" 3968 / 175 SX
 NO CORES
 DSTS TAKEN - DETAILS NA
 MICT - CO, PF (ARB) 3866-3869, AC 250 GAL (MA), SWB
 DWN, GSO & WTR, POP, P WTR W/SO, OFF PMP,
 SQZ'D PFS W/CMT, PF (LKC) INTV NA, TSTD, POP, P
 10 BOPD, 3/1/82, DECL TO 6-7 BOPD, OFF PMP, RE-PF
 (ARB) 3865-3875, SWB DWN, SO, AC 5 BBLs (MA), POP,
 P 6-10 BOPD, 8/23/82, P 6-7 BOPD, 11/12/82,
 COMMINGLED,

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

Date: *8-15-2002*

Olivia:

Please Send Invoice To:

**Great Eastern Energy & Development Corporation
P.O. Box 150
Bogue, Kansas 67625**

Thank-You.

Sheila

District #4

Hays, Kansas 67601