

4-19

4-041666

D-19,567

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15-163-20863-00-00  
SW SW NW /4 SEC. 26, 09 S, 20 W  
2970 feet from S section line  
4950 feet from E section line

Operator license# 8914 Lease Mead-Marcotte well # 1

Operator: H & C Operating County Rooks

Address: P.O. Box 86  
Plainville, Kansas 67663  
Well total depth 4070 <sup>132.28</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well     , Gas well     , Input well     , SWD X, D & A     

Plugging contractor: Allied Cementing License#     

Address: Hays, Kansas 67601

Company to plug at: Hour: 11:00A.M. Day: 19 Month: April Year: 95

Plugging proposal received from: Bob Plante

Company: Allied Cementing Phone:     

Were: 8 5/8" - 266' cwc with 200 sxs. cement.  
4 1/2" casing set at 3970' w/75 sxs. cement.  
Cemented w/375 sxs. circulate to surface.  
Ordered 150 sxs. common with 1/4# F.C. plus 200 sxs. 60/40 pozmix - 6% gel with 1/4# F.C.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 3:00P.M., Day: 19, Month: April, Year: 95

Actual plugging report: Actual plugging report: R.I.H. with tubing to T.O.F. at 1350' circulated hole - clear of all mud. P.O.O.H. Took pump rate - 2 1/2 bbl. per. min. to P.S.I. Ran I.H. with 150' of 1" joint. Tubing on bottom of 2 3/8" tubing - ran tubing past T.O.F. at 1350' to a depth of 1483' - pumped 150 sxs. common with 1/4# F.C. - no returns at surface. Pulled to 12' above T.O.F. Wait on water for 30-40 min. Hooked-up to tubing - attempt to pump cement to circulate. Tubing pressured up to 3000#. Plugged. Pulled tubing to clear obstruction-iron sulphide packed at 1"to2" swedge. R.I.H. with tubing to top of cement at 1331'. Pumped 100 sxs. 60/40 pozmix - 8% gel to circulate at surface. Pulled tubing. Hooked-up to 4 1/2" casing - squeezed 80 sxs. cement with Max. P.S.I. 200#. S.I.P. 100#. Hooked-up to annulus of 4 1/2" x 8 5/8" S.P. - squeezed in 20 sxs. cement with Max. P.S.I. 300#. S.I.P. 200#.

Remarks:       
Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL

I did[ X ] / did not[      ] observe the plugging.

Dennis Hamel  
(agent)

**INVOICED**

DATE 5-2-95  
INV. NO. 42722

STATE CORPORATION COMMISSION  
APR 27 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS