

8-2  
4- 060328

145  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,206 -00-00  
133'NW of  
SW NE SE /4 SEC. 26 , 09 S, 20 W  
1780 feet from S section line  
1020 feet from E section line

Operator license# 30606

Lease Marcotte well #1-26

Operator: Murfin Drilling Co., Inc.

County Rooks

Address: 250 N. Water  
#300  
Wichita, Kansas 67202

Well total depth 3845 feet <sup>124.96</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 277 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling Co., Inc. License#30606

Address: Wichita, Kansas 67202

Company to plug at: Hour:2:00P.M. Day: 2 Month: August Year: 92

Plugging proposal received from: Rodney Farr

Company: Murfin Drilling Co., Inc. Phone: 316-267-3241

Were: Order 215 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour:2:00P.M., Day: 2, Month: August, Year: 92

Actual plugging report:

- 1st. plug at 3730' w/25 sxs. - Arbuckle
- 2nd. plug at 1660' w/25 sxs. - Anhydrite 1637' - 1687'
- 3rd. plug at 995' w/100 sxs.- Dakota 695' - 995'
- 4th. plug at 330' w/40 sxs. - Surface pipe 277'
- 5th. plug at 40' w/10 sxs.
- 15 sxs. in Rathole.

8/5/92

Remarks: Allied Cementing

RECEIVED

Condition of casing(in hole):GOOD      BAD      Anhy.plug: YES X NO      STATE CORPORATION COMMISSION

Bottom plug(in place): YES X , CALC      , NO      Dakota plug: YES X , NO     

Plugged through TUBING      , CASING      . Elevation: 219 AUG 5 1992

I did      did not [ X ] observe the plugging.

[Signature]  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 9-11-92

(agent)

INV. NO. 36091

Form CP-2/3

[Signature]