

64000499 12-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,256-00-00

NE NE SE/4 SEC 26, 09 S, 20 W
2310 feet from S section line
440 feet from E section line

Operator license# 30537

Lease: MARCOTTEE Well # 1

Operator: Venture Resources Inc.

County: ROOKS

Address: 518 17th Street
suite 1130
Denver, CO

Well total depth: 3800 feet
Conductor pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 264 feet

123.50

Abandoned Oil well: 80202 Gas Well: Input Well: SWD Well: D & A: X

Plugging contractor: EMPHASIS OIL OPERATIONS License: 08241

Address: RUSSELL, KANSAS 67665

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: LARRY LANGHOFFER

Company: EMPHASIS OIL OPERATIONS Phone:

Were: Spot all plugs through drill with heavy mud between all plugs.

1st plug @ 3739 feet with 25 sacks

Rat hole: 15 sacks

2nd plug @ 1635 feet with 25 sacks

Mouse hole: sacks

3rd plug @ 980 feet with 100 sacks

Wiper plug @ 40 feet

4th plug @ 310 feet with 40 sacks

5th plug @ 40 feet with 10 sacks

Plugging proposal received by: DAVID WANN

Plugging operations attended by agent? All[], Part[], None[X]

Completed: hour: 3:00 PM, Day: 20, Month: December, Year: 1994

Actual plugging report: Hole reported plugged as above

Order 215 sx 60/40 posmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2182 G Anhydrite depth: 1635 feet, Anhy. plug: T
Dakota plugged: T Bottom hole plug in place (A/E/N): A
Plugged through drill pipe: T
Arbuckle: 3739 Cemented by: ALLIED

I did [] / did not [X] observe the plugging.

INVOICED

(TECHNICIAN)

DATE 1-5-95
REV. NO. 41983

12/27/94
form CP-2/3
WICHITA, KANSAS