

2-18-88 15-163-00130-00-00 139 R

6 031038

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1957

SE SE NW, SEC. 27, T 9 S, R 20 W/EX
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258

Lease Name Tribble Well # 1

Operator: D. G. Hansen Trust
Name & Address: Box 187
Logan, Ks. 67646

County Rooks 126.17

Well Total Depth 3882 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 181

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Plainville, Ks.

Company to plug at: Hour: PM Day: 18 Month: Feb Year: 19 88

Plugging proposal received from Johnnie Parsons

(company name) Hansen Trust (phone) _____

were: 8 5/8" set at 181 cwc. 5 1/2" set at 3834' w/125 sks. 4 1/2" liner to 3880' cwc.

5 1/2" squeezed w/cement at 50'. Order 200 sks ATL Cement Blend 65/35 Poz 10% Gel

2% Dical 5 sks Hulls. Allied Cement Co. OWS Water truck and company truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:45 PM Day: 18 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/150 sks Cement Blend w/4 sks Hulls mixed into

Max Psi 700#. Close in 300#. Squeezed 8 5/8" - 5 1/2" Annulus w/50 sks Cement Blend

w/1 sk Hulls mixed into Max Psi 400#. Close in at 200# Psi. Plug complete.

STATE CORPORATION COMMISSION

4/22/88

APR 22 1988

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If ~~not~~ observe this plugging.

DATE 4-26-88

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INV. NO. 20452