

6- 100434

7-11

135  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,173-00-00

C NE /4 SEC. 27, 09 S, 20 W  
3960 feet from S section line  
1320 feet from E section line

Operator license# 3456

Lease Rathburn well # 11

Operator: AFG Energy, Inc.

County Rooks

Address: P.O. Box 605  
Russell, Kansas 67665

Well total depth 3900 feet <sup>126.75</sup>  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 267 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: ??? Day:        Month:        Year:       

Plugging proposal received from: Jack Fox

Company: Emphasis Drilling Operations phone:       

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3830 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1750 feet " 25 " Mousehole:        sacks

3rd plug @ 1060 feet " 100 "

4th plug @ 310 feet " 40 "

5th plug @ 40 feet " wiper plug & 10 sx

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 11:30am, Day: 11, Month: July, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 215 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2257 GL, Anhydrite depth: 1749 - 1786 feet

Did        penetrate Arbuckle, cemented by Allied

I did        observe the plugging.

David K. Wann P.I.R.T. II  
(agent)

*J. S.*

DATE 9-5-91

INV. NO. 32926

RECEIVED  
STATE CORPORATION COMMISSION  
8/23/91  
AUG 23 1991

STATE CORPORATION COMMISSION  
WICHITA, KANSAS

INVOICED