

4-041633 12-1 163 20652-0000
API number: 15- - N/A

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING E2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SE /4 SEC. 27 , 09 S, 20 W
2310 feet from S section line
825 feet from E section line

Operator license# 5337 Lease Hinkhouse well # 23

Operator: Nadel & Gussman County Rooks

Address: 3200 First National Tower Well total depth 3886 feet ^{126.30}
Tulsa, OK 74103 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 306 feet
w/175 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 1 Month: December Year: 94

Plugging proposal received from: John 'Art' Rolo

Company: Nadel & Gussman Phone: 913-434-2916

Were: 5 1/2" casing set @ 3886' w/150 sxs. cement.
Anhy @ 1775' - Dakota @ 1075'.
Order 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls and
12 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 1:45P.M., Day: 1, Month: December, Year: 94

Actual plugging report: R.I.H. with tubing to 3880'. Spotted 12 sxs.
gel, followed with 60 sxs. cement with 200# hulls - pulled to 1800'.
Spotted 150 sxs. to circulate at surface - pulled tubing. Squeezed
casing with 50 sxs. cement. Max. P.S.I. 300#. S.I.P. 100#.
8 5/8" S.P. - squeezed 40 sxs. cement with 100# hulls in cement.
Max. P.S.I. 350#. S.I.P. 100#.

RECEIVED
STATE CORPORATION COMMISSION
12/12/94
DEC 12 1994

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X / did not observe the plugging. Dennis L. Hamel

INVOICED
DATE 12-12-94
INV. NO. 41899

(agent)
Form CP-2/3

CONSERVATION DIVISION
WICHITA, KANSAS