

7-17-88

API NUMBER 15-163-01737-0000

To: 6 020468
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N L N/2 SE, SEC. 27, T 9 S, R 20 W/E

1320 FE feet from S section line
1320 FS feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Hinkhouse Well # 5

Operator: Nadel and Gussman

County Rooks 124.77

Name & Address 3232 First Nat. Tower

Well Total Depth 3839-3800 feet

Tulsa, Ok. 74103

Conductor Pipe: Size feet

918-583-3333

Surface Casing: Size 8 5/8 feet 135 w/115

Abandoned Oil Well x Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Nadel and Gussman License Number 5337

Address

Company to plug at: Hour: 9:00AM Day: 17 Month: June Year: 19 88

Plugging proposal received from Frank Neff

(company name) (phone)

were: Order 65/35 Poz 10% Gel 2% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss. 5 Hulls.

5 1/2" at 3838' w/125 sks. Open hole 3838' - 3839'.

Plug hole at 1400' w/200 sks. Holes at 1810' w/280 sks 960' w/170 sks. 1100' w/170 sks.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 10:15AM Day: 17 Month: June Year: 19 88

ACTUAL PLUGGING REPORT 50 sks cement followed w/100 sks with Hulls and 100 sks

in Annulus. 8 5/8" casing 600 max 200 shut in. 5 1/2" 800# 600# total 225 sks.

RECEIVED
STATE CORPORATION COMMISSION
7/12/88
JUL 12 1988

Remarks: By Allied.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Gilbert Balthazor (TECHNICIAN)
Gilbert Balthazor

DATE 7-21-88

INV. NO. 21532

G.S.