

4-041360

3-31

39  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,537 -00-00

SW NE /4 SEC. 27, 09 S, 20 W  
3300 feet from S section line  
1980 feet from E section line

Operator license# 3456

Lease Rathbun well # 7

Operator: A.F.G. Energy, Inc.

County Rooks

Address: P.O. Box 605  
Russell, Kansas 67665

Well total depth 3900 feet <sup>126.75</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 244 feet  
w/150 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 31 Month: March Year: 92

Plugging proposal received from: Terry Piesker

Company: A.F.G. Energy, Inc. Phone:                     

Were: 5 1/2" casing set @ 3900' w/150 sx. Perf. @ 3834' - 3864'.  
Squeezed @ 1100' w/150 sx. 1520' w/120 sx. 1480' w/70 sx. 950' w/110 sx.  
4 1/2" line from 1689' to surface w/60 sx.  
Order 400 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:15P.M., Day: 31, Month: March, Year: 92

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 25 sx.  
cement followed w/225 sx. cement with 1/4# flocele plus 500# hulls in  
cement - Max.1200# - S.I. 1000# Hooked-up to 8 5/8" S.P. Pumped in  
100 sx. cement with 1/4# flocele plus 100# hulls. Max. 800#. S.I. 400#.

Remarks:

Condition of casing(in hole): GOOD X BAD     Any plug: YES X NO      
Bottom plug(in place): YES X CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , Elevation:                      GL    

I did X observe the plugging

**INVOICED**  
DATE 4-21-92  
SER. NO. 34958

RECEIVED  
APR 15 1992  
4/15/92  
CONSERVATION DIVISION  
Wichita, Kansas

*Dennis L. Hamel*

(agent)  
Form CP-2/3