

5-26-88

6 020461

163-22,359-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
100' N of C, SW SEC. 32, T 9 S, R 20 W/

1420 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

Lease Name Tucker Well # 7

Operator: B J Oil Co

County Rooks 126.75

Name & Address 1503 Vine St. Suite B

Well Total Depth 3900 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 178' w/130

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B J Collins License Number 5465

Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 26 Month: May Year: 19 88

Plugging proposal received from J B Collins

(company name) (phone)

were: Perf 3838' - 44' and 3830' - 34'. 5" - 3898' w/150 sks. 5 1/2" shot at 1750'

w/4 holes and 1300' w/3 holes. Anhy 1750' Bottom of Dakota 1300'. Fluid levels dry.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00Pm Day: 26 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing 60/40 Poz 6% Gel 3% Ca Cl. 25 sks and 275 sks mixed w/6 sks Hulls. 500 Max. 200 shut in. Pumped down 8 5/8" 75 sks w/6 sks Hulls.

Max pressure 800 lbs. Shut in 200#. By Allied

7/6/88

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If paid, please observe this plugging.)

DATE 7-7-88

INV. NO. 21195

Signed Gilbert Balthazor (TECHNICIAN)