

9-27 15-163-19347-00-00

4-041541

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 5-28-59

SW SW SE /4 SEC. 32 , 09 S, 20 W
330 feet from S section line
2310 feet from E section line

Operator license# 5363

Lease Miller well # 45

Operator: Berexco, Inc.

County Rooks

123.53

Address: Box 723
Hays, Kansas 67601

Well total depth 3801 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 203 feet
w/150 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 27 Month: September Year: 93

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone:

Were: 5 1/2" casing set @ 3799'. Perf. @ 3799' - 3801'. Perfs.
Anhy. @ 1970' - Dakota @ 800'. D.V. @ anhy. (1700') with 600 sxs.
Casing squeezed at 1234' - 1265' with 15 sxs. Squeeze at 1385' - 16'
with 25 sxs. Squeeze at 1393' - 1409' with 20 sxs. Squeeze at 2377' -
2408' with 120 sxs. Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4#
F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 27, Month: September, Year: 93

Actual plugging report: R.I.H. with tubing to 3600'. Spot 50 sxs. 60/40
pozmix with 200# hulls. Pull to 2500' - spot 50 sxs. cement with 200#
hulls. Pull to 1700' - spot 50 sxs. cement. Pull to 800' - spot 60 sxs.
cement to circulate to surface. Pull tubing. Squeeze 25 additional
sxs. cement.

RECEIVED
STATE CORPORATION COMMISSION
11/19/93
NOV 19 1993

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did [] observe the plugging.

Dennis L. Hamel

INVOICED
DATE 11-22-93
INV. NO. 39264

(agent)