

15-163-19348-00-00

4-070086

D-07,320

TO: 1-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - N/A

NW SW SW /4 SEC. 32, 09 S, 20 W
1050 feet from S section line
~~4950~~ 4800 ^{KCC} _{TAP} feet from E section line

Operator license# 30177

Lease: Tucker Well # 5

Operator: GPS Oil Lease Operations

County: Rooks 137.77

Address: P.O. Box 119
Inman, Kansas 67546-0119

Well total depth 4239 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 210 feet
W/150 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: GPS Oil Lease Operations License# 30177

Address: P.O. Box 119 - Inman, Kansas 67546

Company to plug at: Hour: 10:00 A.M. Day: 29 Month: January Year: 1998

Plugging proposal received from: Ray Gilbert

Company: GPS Oil Lease Operations Phone: 316-585-2560

Were: 5 1/2" set at 3978' w/150 sxs. D.V. Tool at 1788' w/400 sxs.
4 1/2" linner set at 3950' w/350 sxs cwc.
2 3/8" tubing parted at 1157' with packer set at 3900'.
Tubing still open and taking water. Unable to recover any tubing. Tubing was in bad shape.
Plug according to KCC Rules and Regulations.
Ordered 245 sxs of Halliburton Mid Con II with 800# hulls.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:15 A.M., Day: 29, Month: January, Year: 1998

Actual plugging report: Halliburton pumped 60 bbls of fresh water at 3.5 bpm 600#.
Pumped 125 sxs of Mid Con II (70 bbls of slurry) down 4 1/2" casing. Max. P.S.I. 1000#.
S.I.P. 750#. After one hour 50# shut in.

Remarks: Tubing parted at 1157'. Packer at 3900'.

Condition of casing(in hole): GOOD BAD

Bottom plug(in place): YES , CALC , NO

Plugged through TUBING , CASING

I did / did not observe the plugging.

Anhy.plug: YES NO

Dakota plug: YES , NO

Elevation: 2255 GL

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 2-6-98

INV. NO. 50036

RECEIVED
KANSAS CORP COM
2/15/98
1998 FEB 15 A 11:23