

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02884-00-01
Spot: CSWSWSE Sec/Twnshp/Rge: 12-9S-21W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: EICHMAN Well Number: 5
County: GRAHAM Total Vertical Depth: 3672 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 247 150 SXS CMT
Production: Size 5.5 feet: 3671 250 SXS CMT
Liner: Size feet:

919.34

Well Type: SWD UIC Docket No: D19085.0 Date/Time to Plug: 09/20/2001 9:00 AM
Plug Co. License No.: 5285 Plug Co. Name: HANSEN, DANE G. - TRUST
Proposal Rcvd. from: RICHARD WALLGREN, SR. Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Order 300 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/20/2001 11:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 247' w/150 sxs cwc. 5 1/2" set at 3671' w/250 sxs.
Squeezes 1032' w/250 sxs.
To surface 2217' - 2248' w/75 sxs - 1200' w/150 sxs - 2050' w/100 sxs - 2904' w/50 sxs.
New holes in casing below 2500'.
O.H. 3671' - 3986'.
Squeezed 5 1/2" with 300 sxs cement blend with 800# hulls mixed in to Max. P.S.I. 100#. Held.
Plug complete.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

RECEIVED

OCT 03 2001

KCC WICHITA

SEP 25 2001

INVOICE

DATE 10-03-01

INV. NO. 2002060710

Form CP-2/3

D. G. HANSEN

#5

EICHMAN

12-9-21W 22
SW SW SE

Contr. C-G DRILLING COMPANY

GRAHAM

County

E. 2140

Comm. 4-4-50


Comp. 6-16-50

IP 107 BOPD

PHY POT

Tops	Depth	Datum	Casing
ANH	1630	+ 610	8" 246 ACID 500
			5" 3666½ SWB 4½ BOPH
ARB	3666	- 1526	
T.D.	3672	- 1532	

MOREL E. POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS